


ERECTED DIMENSIONS


Lifts above 60 tonnes are limited to 15 m/s wind speed

FORCES AT GROUND LEVEL



BASE FORCES, 167.0 m (109.8 m mast)

Wind speed	IN SERVICE 15 m/s	OUT OF SERVICE 40 m/s
M (kNm)	27850	26800
N (kN)	6580	5130
Q (kN)	120	410
M _T (kNm)	800	0
Deflection, masth. (m)	1.500	0.850
Tilt, masth. (degrees)	1.100	0.500
Corner load (kN) 16x16m BX	3000	2500



INHALTSVERZEICHNIS



- 1.BLATT: AUFSTELLPLAN „MAßE“ MIT LASTFÄLLEN
 - 2.BLATT: MONTAGESCHRITTE
 - 3.BLATT: GRUNDGESTELL MIT BRITTPLATTE, 2 X VORHANDEN
 - 4.BLATT: GRUNDGESTELL
 - 5.BLATT: KLETTERKÄFIG (2 X VORHANDEN)
 - 6.BLATT: LASTENDIAGRAMM
 - 7.BLATT: GEWICHTE
 - 8.BLATT: FOTO MIT ZUSÄTZLICHEN WINDEN
 - 9.BLATT: FOTO STROMAGGREGAT
 - 10.BLATT: FOTO DER BRITTPLATTEN
 - 11.BLATT: FOTO TURMENDE MIT KLETTERKÄFIG
- ERECTION MANUEL - AUFBAUHINWEISE

THIS DRAWING IS THE PROPERTY OF KRAL CRANES A/S AND MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS WITHOUT PERMISSION.

1.13.2017

K1500L

Lifts above 60 tons are limited to 15 m/s wind speed



2008 (2012) 15 m/s @ 1.00 g (1.00 g) (1.00 g)

Wind speed	IN SERVICE 15 m/s	OUT OF SERVICE 40 m/s
u (km/h)	3750	5800
v (km/h)	650	2150
w (km/h)	170	310
u ₁₀ (km/h)	800	0
Deflection, main (m)	1.500	0.850
Tilt, main (degrees)	1.60	0.50
Corner load (kN)	3000	2500
Tether DR		

PERFORMANCE

HOIST MOTOR	160 kW
4 PARTS	
0-10 t	0-52 m/min
10-60 t	0-12 m/min
60-120 t	0-6 m/min
Unstated Full load	3:00 min/sec
	4:00 min/sec
10-68.5 m	0-6.5 rpm
3 x 40 V, 60 Hz	Control voltage 24 VDC - 230 VAC

K1500L LOAD CHART
MAIN HOIST 4-FALL
69 m BOOM

RADIUS (METRES)	BOOM ANGLE (DEGREES)	S.W.L. (TONNES)
10.1	86.0	125.0
12.5	84.0	125.0
15.0	81.9	100.4
17.5	79.8	82.1
20.0	77.6	68.5
22.5	75.5	57.8
25.0	73.3	49.3
27.5	71.0	42.4
30.0	68.8	36.6
32.5	66.5	31.7
35.0	64.1	27.5
37.5	61.7	23.9
4.00	59.2	20.8
4.25	56.6	18.1
4.50	54.0	15.7
4.75	51.2	13.5
5.00	48.3	11.6
5.25	45.3	9.8
5.50	42.0	8.2
5.75	38.5	6.7
6.00	34.7	5.4
6.25	30.5	4.2
6.50	25.4	3.1
6.75	18.6	2.2
6.85	15.0	1.8

KRAL CRANES A/S

Model: K1500L

Scale: 1:300

Drawn: [Signature]

Checked: [Signature]

Approved: [Signature]

Project: K1500L

Client: [Name]

Address: [Address]

Phone: [Phone]

Fax: [Fax]











Website: [Website]

Copyright © 2008 KRAL CRANES A/S

C1-00-00091001-08


2 Belt

Span 23




KRÖLL 150012 A	MODEL	REMARKING	318	SAME	TECH
CON. 150012 A	SCALE	1:250			
DESIGNER	DESIGN	DATE			
INSTALLER	INSTALLATION	DATE			
OPERATOR	OPERATION	DATE			
KRÖLL CRANES A/S		K1500L			
NORLANDSVEJ 2 2850 LINDØS DENMARK		M33 tower sections			
Phone: +45 46 95 10 00		TECH. NO. C1-00.00091001-08			


3 Blatt



Rev 01 (150617) NKS: 90H is updated, "90M" text added.
 Rev 02 (150617) NKS: Item 7 + 8 + 12 + 15 + 16 + 17 released for production.
 8 008 (Item 10) released by 63532; Item 13 deleted; Item 53 + 54 added.



B-B (1:60)



C-C (1:60)

NO	ITEM NO	NAME	UNIT	QTY	REMARKS
1	1	BASE	1	1	
2	2	
3	3	
4	4	
5	5	
6	6	
7	7	
8	8	
9	9	
10	10	
11	11	
12	12	
13	13	
14	14	
15	15	
16	16	
17	17	
18	18	
19	19	
20	20	
21	21	
22	22	
23	23	
24	24	
25	25	
26	26	
27	27	
28	28	
29	29	
30	30	
31	31	
32	32	
33	33	
34	34	
35	35	
36	36	
37	37	
38	38	
39	39	
40	40	
41	41	
42	42	
43	43	
44	44	
45	45	
46	46	
47	47	
48	48	
49	49	
50	50	
51	51	
52	52	
53	53	
54	54	



KRÖLL CRANES AS
 KROLLKRAANEN B.V. - DE WITTE WEG 10 - 1315 AA AMSTERDAM - THE NETHERLANDS
 TEL: +31 (0)20 616 6000 FAX: +31 (0)20 616 6001
 WWW.KROLLCRANES.COM

DRIVING
C1-01.00061660-02

833 16416m main assembly

DATE: 2015-12-21

5 Blatt



Rev 02: Pos 35 added
Rev 01: Pos 34 added

NO	DESCRIPTION	UNIT	QTY	REMARKS
1	WALVE 111000018	WALVAN M18	8	
2	WALVE 111000019	WALVAN M18	8	
3	WALVE 111000020	WALVAN M18	8	
4	WALVE 111000021	WALVAN M18	8	
5	WALVE 111000022	WALVAN M18	8	
6	WALVE 111000023	WALVAN M18	8	
7	WALVE 111000024	WALVAN M18	8	
8	WALVE 111000025	WALVAN M18	8	
9	WALVE 111000026	WALVAN M18	8	
10	WALVE 111000027	WALVAN M18	8	
11	WALVE 111000028	WALVAN M18	8	
12	WALVE 111000029	WALVAN M18	8	
13	WALVE 111000030	WALVAN M18	8	
14	WALVE 111000031	WALVAN M18	8	
15	WALVE 111000032	WALVAN M18	8	
16	WALVE 111000033	WALVAN M18	8	
17	WALVE 111000034	WALVAN M18	8	
18	WALVE 111000035	WALVAN M18	8	
19	WALVE 111000036	WALVAN M18	8	
20	WALVE 111000037	WALVAN M18	8	
21	WALVE 111000038	WALVAN M18	8	
22	WALVE 111000039	WALVAN M18	8	
23	WALVE 111000040	WALVAN M18	8	
24	WALVE 111000041	WALVAN M18	8	
25	WALVE 111000042	WALVAN M18	8	
26	WALVE 111000043	WALVAN M18	8	
27	WALVE 111000044	WALVAN M18	8	
28	WALVE 111000045	WALVAN M18	8	
29	WALVE 111000046	WALVAN M18	8	
30	WALVE 111000047	WALVAN M18	8	
31	WALVE 111000048	WALVAN M18	8	
32	WALVE 111000049	WALVAN M18	8	
33	WALVE 111000050	WALVAN M18	8	
34	WALVE 111000051	WALVAN M18	8	
35	WALVE 111000052	WALVAN M18	8	
36	WALVE 111000053	WALVAN M18	8	
37	WALVE 111000054	WALVAN M18	8	
38	WALVE 111000055	WALVAN M18	8	
39	WALVE 111000056	WALVAN M18	8	
40	WALVE 111000057	WALVAN M18	8	
41	WALVE 111000058	WALVAN M18	8	
42	WALVE 111000059	WALVAN M18	8	
43	WALVE 111000060	WALVAN M18	8	
44	WALVE 111000061	WALVAN M18	8	
45	WALVE 111000062	WALVAN M18	8	
46	WALVE 111000063	WALVAN M18	8	
47	WALVE 111000064	WALVAN M18	8	
48	WALVE 111000065	WALVAN M18	8	
49	WALVE 111000066	WALVAN M18	8	
50	WALVE 111000067	WALVAN M18	8	
51	WALVE 111000068	WALVAN M18	8	
52	WALVE 111000069	WALVAN M18	8	
53	WALVE 111000070	WALVAN M18	8	
54	WALVE 111000071	WALVAN M18	8	
55	WALVE 111000072	WALVAN M18	8	
56	WALVE 111000073	WALVAN M18	8	
57	WALVE 111000074	WALVAN M18	8	

KRILL CRANES AIS
 KONINKRIJK DER NEDERLANDEN
 PO BOX 15133 HIL
 1151 AB AMSTERDAM THE NETHERLANDS
 TEL: +31 (0) 20 674 1111
 WWW.KRILLCRANES.NL

CR133 main assembly

DRUING NO: **C1-08.00061770-02**

REVISIONS:

NO	DESCRIPTION	DATE
1	ISSUE FOR PRODUCTION	2008-03-10

SCALE: 1:50

TOTAL WEIGHT: 34114 kg

CR133 main assembly

30-08-2015 10:07




6 Blatt

KRÖLL

K1500L – Heights under hook

Radius	Boom length: 68.5 m														
	9	10	12.5	15	20	25	30	35	40	45	50	55	60	65	68.5
2 x M33	100.6	100.5	100.1	99.6	98.3	96.7	94.5	91.9	88.7	84.9	80.2	74.6	67.1	56.9	44.8
3 x M33	108.4	108.3	107.9	107.4	106.1	104.5	102.3	99.7	96.5	92.7	88.0	82.4	74.9	64.7	52.6
4 x M33	116.2	116.1	115.7	115.2	113.9	112.3	110.1	107.5	104.3	100.5	95.8	90.2	82.7	72.5	60.5
5 x M33	124.0	123.9	123.5	123.0	121.7	120.1	117.9	115.3	112.1	108.3	103.6	98.0	90.5	80.3	68.2
6 x M33	131.8	131.7	131.3	130.8	129.5	127.9	125.7	123.1	119.9	116.1	111.4	105.8	98.3	88.1	76.0
7 x M33	139.6	139.5	139.1	138.6	137.3	135.7	133.5	130.9	127.7	123.9	119.2	113.6	106.1	95.9	83.8
8 x M33	147.4	147.3	146.9	146.4	145.1	143.5	141.3	138.7	135.5	131.7	127.0	121.4	113.9	103.7	91.6
9 x M33	155.2	155.1	154.7	154.2	152.9	151.3	149.1	146.5	143.3	139.5	134.8	129.2	121.7	111.5	99.4
10 x M33	163.0	162.9	162.5	162.0	160.7	159.1	156.9	154.3	151.1	147.3	142.6	137.0	129.5	119.3	107.2
11 x M33	170.8	170.7	170.3	169.8	168.5	166.9	164.7	162.1	158.9	155.1	150.4	144.8	137.3	127.1	115.0
12 x M33	178.6	178.5	178.1	177.6	176.3	174.7	172.5	169.9	166.7	162.9	158.2	152.6	145.1	134.9	122.8





KROLL

E. J. Blatt

K1500L – Detailed load chart

Radius [m]	Boom angle [deg]	SWL [tons]	Radius [m]	Boom angle [deg]	SWL [tons]	Radius [m]	Boom angle [deg]	SWL [tons]
9,0	87,0	125,0	29,0	69,8	40,2	49,0	49,6	13,1
9,5	86,6	125,0	29,5	69,3	39,1	49,5	49,0	12,7
10,0	86,2	125,0	30,0	68,9	37,9	50,0	48,4	12,3
10,5	85,8	125,0	30,5	68,4	36,9	50,5	47,8	12,0
11,0	85,3	125,0	31,0	67,9	36,0	51,0	47,2	11,6
11,5	84,9	125,0	31,5	67,5	35,0	51,5	46,6	11,2
12,0	84,5	125,0	32,0	67,0	34,0	52,0	46,0	10,9
12,5	84,1	125,0	32,5	66,6	33,0	52,5	45,4	10,5
13,0	83,7	120,5	33,0	66,1	32,2	53,0	44,8	10,2
13,5	83,2	116,0	33,5	65,6	31,3	53,5	44,1	9,8
14,0	82,8	111,5	34,0	65,1	30,5	54,0	43,5	9,5
14,5	82,4	107,0	34,5	64,7	29,7	54,5	42,8	9,2
15,0	82,0	102,5	35,0	64,2	28,8	55,0	42,2	8,8
15,5	81,6	98,8	35,5	63,7	28,1	55,5	41,5	8,5
16,0	81,1	95,1	36,0	63,2	27,3	56,0	40,8	8,2
16,5	80,7	91,4	36,5	62,8	26,6	56,5	40,1	7,9
17,0	80,3	87,7	37,0	62,3	25,9	57,0	39,4	7,6
17,5	79,9	84,0	37,5	61,8	25,2	57,5	38,7	7,3
18,0	79,4	81,2	38,0	61,3	24,5	58,0	37,9	7,0
18,5	79,0	78,4	38,5	60,8	23,9	58,5	37,2	6,8
19,0	78,6	75,7	39,0	60,3	23,2	59,0	36,4	6,5
19,5	78,1	72,9	39,5	59,8	22,6	59,5	35,6	6,2
20,0	77,7	70,1	40,0	59,3	22,0	60,0	34,8	5,9
20,5	77,3	68,0	40,5	58,8	21,4	60,5	34,0	5,7
21,0	76,8	65,8	41,0	58,3	20,8	61,0	33,2	5,4
21,5	76,4	63,7	41,5	57,8	20,3	61,5	32,3	5,2
22,0	76,0	61,5	42,0	57,3	19,7	62,0	31,4	4,9
22,5	75,5	59,3	42,5	56,7	19,1	62,5	30,5	4,7
23,0	75,1	57,6	43,0	56,2	18,6	63,0	29,5	4,4
23,5	74,7	55,9	43,5	55,7	18,1	63,5	28,6	4,2
24,0	74,2	54,2	44,0	55,2	17,6	64,0	27,5	4,0
24,5	73,8	52,4	44,5	54,6	17,1	64,5	26,5	3,8
25,0	73,4	50,7	45,0	54,1	16,6	65,0	25,4	3,5
25,5	72,9	49,3	45,5	53,5	16,2	65,5	24,2	3,3
26,0	72,5	47,9	46,0	53,0	15,7	66,0	22,9	3,1
26,5	72,0	46,5	46,5	52,4	15,3	66,5	21,6	2,9
27,0	71,6	45,1	47,0	51,9	14,8	67,0	20,2	2,7
27,5	71,1	43,7	47,5	51,3	14,4	67,5	18,6	2,5
28,0	70,7	42,5	48,0	50,8	13,9	68,0	16,8	2,3
28,5	70,2	41,4	48,5	50,2	13,5	68,5	15,0	2,1

K1500L weights, 179 m hook height

Top crane including slew mount	:	232 tons
Tower sections and foundation plates	:	347 tons
Total crane weight	:	579 tons

Deck assembly 68,9 tons

Deck	25,2
Slew mount	9,5
Slew ring and bolts	3,3
Hoist winch	11,0
Hoist wire	6,6
Luff winch	4,8
Luff wire	1,3
Slew drives	0,6
Driver's cabin assy	4,9
Misc.	1,7

Counterweight 100,0 tons

Counterweights	100,0
----------------	-------

Toptower/Mast assembly 15,2 tons

Legs	10,6
Pulleys	1,4
Buffer	0,9
Platforms/ladder	0,8
Misc.	1,5

Boom, 69 m 31,4 tons

Inner	5,6
Extension	4,3
Extension	3,3
Extension	3,3
Extension	3,3
Top	5,8
Tip	4,5
Misc.	1,5

Boom, tagline winch additions 8,9 tons

Tagline system	8,9
----------------	-----

Bridle 2,5 tons

Bridle w/connectors	2,5
---------------------	-----

Pendants 1,9 tons

44 mm ropes, 4 pcs	1,6
Connectors	0,3

Hook block 3,3 tons

Hook block	3,3
------------	-----

Towers, climbing system and foundation plates

CTM33	1 pcs	9,3	9,3 tons
CTM33, winch beam	1 pcs	5,6	5,6 tons
CT33 climber	1 pcs	34,2	34,2 tons
M33-240	12 pcs	15,3	183,6 tons
B33-240, cross and legs	1 pcs	51,5	51,5 tons
Pyramids	4 pcs	1,6	6,4 tons
Foundation plates	4 pcs	14	56 tons

Total 346,6 tons



8 Blatt

S. Blatt



70 Blatt →




17 Blatt




1. ASSEMBLY OF BASE MAST B33

Refer to drawings: C1-01.00061660 B33, pyramids and foundation plate assembly



- The four load distribution plates (7.0 x 2.4 m) are placed on relatively plane ground in a 16.0 x 16.0 m square. The level differences should be within 300 mm corresponding to approx. 2% ground slope.
- Pyramids with integrated hydraulics are placed on top of the load distribution plates within the marked area. Make sure the pyramids are placed in a 16.0 x 16.0 m square. The diagonal distance is theoretically 22.627 m.
- The bottom cross assembled on top of the pyramids. A support at the centre will be needed to prevent deflection. Support capacity at least 40 tons.
Also fit the two side beams, the four lattice rod and the four centre horizontals with pin connections for the bottom mast.
- Use the hydraulics on the pyramids to level the bottom cross.
After jacking the cross in the corners as necessary, the big wrench (parked on the pyramids) is used to turn the spindle and make contact with the bottom cross.
The jacking cylinder has a stroke of 50 mm. If more level adjusting is needed, it must be carried out in several steps.
When all corners are levelled, retract the jacking cylinders, so there is no contact to the bottom cross.

- Fit chains between the bottom cross and the load distribution plates. Use the turnbuckles to tighten the chains.



- Fit the bottom mast B33 onto the bottom cross.
Fit 8 pcs 2.25" bolts between corner members and bottom cross (to not torque tighten).
Fit 8 pcs pins to the horizontals. The pin areas are prepared with supports for hydraulic tools to aid pushing or retracting the pins.



- Fit the four supporting legs between the bottom cross and the top of the B33 mast.
Fit the pins.




- All bolts are torque tightened to 100 %.
The support under the bottom cross centre is removed.
Secondary equipment (remaining ladders, entry stairway, etc.) is fitted.
- The assembly of the B33 bottom mast system is now completed.

Assembled weight : approx. 66 tons (without load distribution plates)

2. PRE-ASSEMBLY OF M33 MAST SECTIONS

Refer to drawings: C1-01.00061640 M33-240/8 (8 bolts per corner)
 C1-01.00061641 M33-240/4 (4 bolts per corner)

- The tower sections come fully welded with platforms and ladders prefitted. The bottom part of the ladder is slidable, so it can fit within the tower section and get pulled out after installation of the tower section.
- The tower is prepared with storage facilities for the 2¼" mast bolts and nut.
 - Support for bolts: The bolts will rest on a plate around the corner and ready to be pulled up, when the next tower section is fitted on top.
 - Storage for one bolt: One bolt is parked away for the bolts support since the inner hole is used as a guide pin when the next tower section is fitted.
 - Nut storage: There is space for 4 nuts on a nut storage tube



- Two tower sections are fitted on top of the base mast B33.

Weight per M33-240 : 15.5 tons

- Slide out the ladders.
- The 2¼" mast bolts are torque tightened to 2950 Nm, see info 5498-03 for instructions.


3. PRE-ASSEMBLY OF CTM33 CLIMBING FRAME

Refer to drawings: C1-01.00061814 CTM33 assembly
 C1-01.00061830 Erection beam with hoist winch


- The CTM section comes fully welded with platforms and ladders prefitted. The bottom part of the ladder is slidable, so it can fit within the tower section and get pulled out after installation of the tower section.
- Make sure that all equipment is fitted including the cable relief bracket.



- Preassemble the erection beam including the hoist winch. Park the trolley as shown where it can be fixed using the pin on top of the beam. Reeve the trolley rope.



- Suspend the erection beam under the CTM33 using the four pins. Reeve the hoist rope from the drum through the CTM33.



The CTM33 and erection beam system is now prepared for fitting.

Assembled weight : Approx. 16.0 tons

4. ASSEMBLY OF CT33 CLIMBING SECTION

Refer to drawing: C1-01.00061770 CT33 main assembly

- Start assembling both side panels consisting of:
 1. Bottom panel with cylinder support
 2. Short intermediate panel
 3. Long upper panel
 4. Diagonal lattice work (7 pcs per side)
 - Fit the
 1. Cylinders to the bottom panels
 2. The fixed claws to the bottom panels
 3. The movable yoke to the cylinder top
 - Using the handle around the cylinders pull the movable yokes "outwards" until they lean against the support rails. Fix the yokes to keep them in place.
 - Raise the side panels and connect them with:
 - 8 pcs horizontal H-beams (4 at the front, 4 at the back)
 - 9 pcs diagonals (6 at the front, 3 at the back)
 - Before tightening all the bolts, check the overall dimensions of the assembled section. Check especially:

Distance between the top $\varnothing 52$ holes is 3895x3315 mm

Distance between the guide rails for the tower sections is 3315 x 3315 mm leaving 7.5 mm clearance for the tower sections
 - Fit the ladders.
 - Fit the platforms
 - Fit the pump station with platform
 - Fit hydraulic hoses and equipment.
 - The assembled CT33 is now ready to be fitted.
- Weight of CT33 complete : 33.0 tons



5. BUILDING THE TOWER TO INITIAL HEIGHT

The B33 bottom mast is prepared with supports for the CT33 climbing section.



Lift the CT33 – using the temporary lifting yokes on top of the CT33 – and fit the CT33 on the supports on B33.

Since there is no M33 towers on top of the B33 to support the CT33, the CT33 is resting in a insecure way.


Secure the CT33 by fitting 4 pcs 10t chains between the lugs on the CT33 to lugs on the outside of the B33 at the platform level.

The chain positions is marked with red on the drawing.

2 pcs M33 towers can be fitted before fitting the CT33. They will support the CT33 with no need for the chains. This erection alternative will, however, require more lifting height to fit the CT33 around the tower.




- Fit – one by one – two pcs M33-240/8 towers inside the CT33. Fit all 2,25" bolts and torque tighten to 100%.
- Fit the CTM33 with erection beam to the top of the tower.



6. TOPTOWER ASSEMBLY

Refer to drawing: P3000-0024-X00 Toptower assembly
 C2-04.00063819 Erection winch assembly

- Pre-assemble the toptower according to the assembly drawing.
- Fit the erection winch at the top just under the sheaves.
 Also fit the wire roller in front of the sheaves and the wire roller on the buffer bracket, both to protect the structures against hanging luffing wires during erection of the crane.
 Fit the wire guide roller under the erection winch.



The toptower is now ready and prepared for fitting on the deck.

Assembled weight : Approx. 17.5 tons (including erection winch)

7. DECK AND MASTHEAD ASSEMBLY

Refer to drawings:	C1-03.00061952	Deck and masthead assembly
	C1-03.00061955	Driver's cabin and suspension assembly
	C1-05.00061715	Hoist winch assembly
	C1-05.00061702	Luff winch assembly
	A5200-0243	Bridle

The deck is supplied with the masthead fitted. If the slew ring is separated from either deck or masthead:

- Each ring on the slew ring has 96 pcs $\varnothing 36$ holes for M33 bolts.
- Before the greased bolts are torque tightened (2580 Nm), it must be ensured that there is full contact between the slew ring and the counterpart, and it must also be ensured that the bolts are not subject to any external forces during tightening of the bolts.
It means that the deck must be supported under the tale, since it otherwise will fall over backwards and prevent proper tightening of the bolt.
If these precautions are not followed, the bolts will either be preloaded inadequately (and reduce slew ring strength) or overtightened (and crack).

When the deck structure, slew ring and masthead is fully bolted together:

- The winches and powerpack are factory-fitted inside the deck.
- Fit the driver's cabin assembly and the right side platform.
- Fit the right and left side platforms near the counterweight area.
- Fit railings.
- Fit the wire roller in front of the deck to prevent structure damage by the hoist wire
- Fit the bridle on its parking platform.


Assembled weight : Approx. 70.0 tons



Use 4 slings/chains with SWL: minimum 30 tons.

Left side slings to be 78 cm longer than right side slings (due to cabin side weight)

To avoid side weight and decrease the total weight, the cabin assembly (5 tons) can be fitted separately after the deck is in place.

It is allowed to walk/sit on the cabin roof to remove the slings






8. FITTING DECK AND TOPTOWER TO TOWER



Depending on available mobile crane capacity, the toptower can be fitted to the deck either when the deck is on the ground or fitted to the tower.

Fitting deck and toptower separately

- Lift the deck/masthead assembly and fit it to the tower
- Fit all 2.25" bolts between masthead and tower. Torque tighten to 100%.
- Fit the counterweights, 11 pcs each 9.1 tons.



- Lift the folded toptower using the lifting lugs at the thick sheave plates. It will angle slightly backwards.
- Use 2 slings with minimum 10 tons SWL
- Fit the front legs to the mast with two pins. The pin areas are prepared with supports for hydraulic tools to aid pushing or retracting the pins.
 - Remove the parking pin between the front legs and rear legs.
 - Let the toptower fall gently backwards until the rear legs also can be pinned to the deck.



Fitting deck and toptower as a unit


- Fit the toptower to the deck as described above.
- Reeve the luffing wire between the sheaves in the toptower and the bridle on the front deck. Refer to drawing A5000-0493, Luff wire reeving diagram. Start reeving the small wire on the erection winch backwards, i.e. pretend the erection drum is the luff anchor (to the right of the toptower sheaves), go through all the sheaves with the right bridle sheave as the first entry, and ending on top of the left sheave on the toptower. Connect it to the fast connector on the luffing wire (on the the luff winch). Pull the erection wire, which is turn reeves the luffing wire through all the sheaves. Pull until the luffing wire can be fixed to the luff anchor.
- Lift the entire deck/toptower unit to the tower.

(Luffing wires)
(not shown)

Assembled weight :
Approx. 87 tons

Use 4 slings/chains with SWL:
minimum 35 tons.


Left side slings to be 78 cm longer than
right side slings unless cabin assembly is
fitted separately.



9. BOOM ASSEMBLY



Refer to drawings :	P4000-0028-X00	Boom assembly, 69 m
	C1-06.00063550	Hook assembly, 125 tons, 4 parts
	A2175-0505	Rope specification (hoist, luffing, pendant and erection pendant)
	A5600-0409	Pendant link assembly
	A9500-0114	Erection pendants assembly
	A5000-0493	Hoist wire (and luffing wire) reeving diagram

- Complete the boom assembly (7 boom sections) according to the drawing. Depending on mobile crane capacity it may be split in two parts consisting of the first 3 sections and the last 4 sections.



- The tip section is only pinned at the top, while resting with the tip "wheel" on the ground.
- Place the hook block near the tip sheaves.
- Fit the pendants on top of the boom.
- Spool out hoist wire.
Full boom assembly: Reeve the wire through the sheaves on top of the boom. Reeve it through the hook block (4 falls) and secure it to hoist anchor with swivel. Secure the hook to the boom tip using an approx. 5m long sling, so the hook will be lifted together with the boom.
Split boom assembly: Reeve the wire through the single hoist sheave on top of the boom and let wire hang out over the 3rd boom section.
- The slew brakes may be released if needed (enabled the crane to slew freely).


Fitting the boom in one piece




- The boom is now ready to be lifted.
When using one mobile crane, the lifting points may need adjusting based on a trial lift.

Total weight of boom, hook, pendants, and tagline winch: 46 tons
Use 4 slings with minimum 20 tons SWL


- When lifting the boom just off the ground, the tip section will slide on the ground. Make the bottom pin connections to the previous boom section when possible. Continue lifting the boom to the deck, while spooling-in hoist wire to keep up with the boom lifting pace.




- Fit the boom to the deck using pins. The pin areas are prepared with supports for hydraulic tool to aid pushing or retracting the pins.
- Fit the erection pendant rope. It may be necessary to raise the boom a little.
- Ease off the mobile crane and check that the boom is hanging properly in the erection pendants before it is released from the mobile crane.



- Lift the bridle from the deck to the bridle platform on the boom. The erection winch at the toptower is also used for this operation to help pulling out the bridle while lifting it:




- The inner boom section is prepared with a couple of rails, where the bridle can be placed temporarily and be pulled – by the erection wire – the last few metres to its final destination on the boom platform ready for connecting to the pendant ropes.



- Connect the bridle to the pendant ropes by pins.
- Operate the luff winch to tighten the luff wires and pendants.
- Operate the hoist winch to tighten the hoist wire. Release the hook from the tip.

Fitting the boom in two pieces


- The hoist wire is reeved and prepared for the outer sections.




- The boom is ready to be lifted.

Total weight of boom, hook, pendants, and tagline winch: 23 tons
 Use 4 slings with minimum 10 tons SWL

- Lift the boom, while spooling-in hoist wire to keep up with the lifting pace.
- Connect the boom to the deck, fit the erection pendants and move the bridle to the boom platform as described above (fitting the boom in one piece).




- Reeve the hoist wire through the sheaves on top of the remaining grounded boom sections. Reeve it through the hook block (4 falls) and secure it to hoist anchor with swivel. Secure the hook to the boom tip using an approx. 5m long sling, so the hook will be lifted together with the boom.



- The outer boom sections are now ready to be lifted.


Total weight of boom, hook, pendants, and tagline winch: 23 tons
 Use 4 slings with minimum 10 tons SWL



- Fit the boom outer sections to the already fitted sections.
- Easy of the mobile crane gently checking that the outer boom sections are hanging properly.
- Operate the hoist winch to tighten the hoist wire. Release the hook from the tip.

10. FINAL STAGES

- Make up remaining electrical connections.
- Check settings of the hoist and luff limits. At first erection the limits must be set.
- Check the radius reading is correct. At first erection the radius reading must be set.
- Check the load indication is correct. At the first erection the load indication must be set by test loading the crane
- Carry out an inspection. Check all connection bolts for 100% torque.
- Check all motions.



- Climb to the required hook height (see section 11).
- The crane is ready for operation.
Maximum wind speed in operation: 15 m/s

